ADDENDUM NO. 1

ADDENDUM DATE: 04/25/2025

ADDENDUM NO.: 1

IFB TITLE: Sespe Creek Overflow Railroad Bridge Repair

IFB NO.: SPBL-2025-01

ADDENDUM SUMMARY

The purpose of the Addendum is to provide additional information and documentation:

- 1. The Exhibit 3 Project Engineering Drawings has been revised for the following sheets:
 - G-002
 - RP-001
 - S-008
 - SC-001
 - SC-002
- 2. Sheet G-002 was updated to indicate the revised sheets.
- 3. Sheet RP-001 has been replaced.
- 4. Sheet S-008 has been voided and replaced by SC-002.
- 5. Sheet SC-001 has been voided and replaced by SC-002.

Changes noted in this addendum have been marked in the documents.

SPBL-2025-01


SESPE CREEK OVERFLOW RAILROAD BRIDGE REPAIR

EXHIBIT 3PROJECT ENGINEERING DRAWINGS

ADDENDUM NO. 1 DATE: 04/25/2025 DATE ISSUED: 04/04/2025

SPBL-2025-01 SESPE CREEK OVERFLOW RAILROAD BRIDGE REPAIR

VENTURA COUNTY TRANSPORTATION COMMISSION SESPE CREEK OVERFLOW RAILROAD BRIDGE REPAIR ON THE SANTA PAULA BRANCH LINE FILLMORE, CA





LOCATION MAP

DATE ISSUED: APRIL 4, 2025

100% SUBMITTAL

CAMERA READY



APPROVED BY: DATE:

SUBMITTED BY: DATE: 3/25/2025

JULINA CORONA, P.E. PROJECE MANAGER, RAILPROS



SHT NO.	DWG. NO.	REV. NO.	TITLE		
GENER	AL				
1	G-001	0	TITLE SHEET		
2	G-002	0	INDEX OF DRAWINGS		
3	G-003	0	STANDARD ABBREVIATIONS		
4	G-004	0	STANDARD SYMBOLS		
5	G-005	0	GENERAL NOTES		
6	G-006	0	SURVEY CONTROL EXHIBIT		
TRACK					
7	TD-001	0 .	TYPICAL SECTION		
8	RP-001	$\binom{2}{2}^{\triangle}$	TRACK PLAN AND PROFILE - STA 98+50 TO STA 110		
9	DIV-001	0	TEMPORARY CREEK DIVERSION PLAN		
STRUC	TURES				
10	S-001	0	GENERAL PLAN NO. 1		
11	S-002	0	GENERAL PLAN NO. 2		
12	S-003	0	GENERAL NOTES AND INDEX OF DRAWINGS		
13	S-004	0	STAGE CONSTRUCTION PLAN		
14	S-005	0	FOUNDATION PLAN		
15	S-006	0	ABUTMENT DETAILS NO. 1		
16	S-007	0 A	ABUTMENT DETAILS NO. 2		
17	S-008	$\left\{\begin{array}{c} z \\ z \end{array}\right\}^{2}$	ROCK SLOPE PROTECTION		
18	S-009	0	BENT DETAILS NO. 1		
19	S-010	0	BENT DETAILS NO. 2		
20	S-011	0	BENT DETAILS NO. 3		
21	S-012	0	GIRDER DETAILS NO. 1		
22	S-013	0	GIRDER DETAILS NO. 2		
23	S-014	0	HANDRAIL REPLACEMENT PLAN		
24	S-015	0	HANDRAIL DETAILS		
25	S-016	0	MISCELLANEOUS DETAILS NO. 1		
26	S-017	0	MISCELLANEOUS DETAILS NO. 2		
GEOTE	CHNICAL				
27	GE-001	0	LOG OF TEST BORINGS		
28	GE-002	0	SOIL LEGEND 1 OF 2 - LOG OF TEST BORINGS		
29	GE-003	0	SOIL LEGEND 2 OF 2 - LOG OF TEST BORINGS		
SCOUR	COUNTER	RMEASURE			
30	SC-001	2	ROCK SLOPE PROTECTION, OWNER'S OPTION		
31	SC-002	\ ₂ \	ROCK SLOPE PROTECTION, OWNER'S OPTION		

FINAL DESIGN (100%) CAMERA READY

RSP SHEETS VOIDED AND REPLACED BY SC-002

0 3/25 ISSUED FOR BID
REV. DATE

4/4/2025 1:27:03 PM USER - jackson.ziegler 2:Engineering\VCTC_SCB_G-002.dgn 2:Engineering\VCTC\Sespe Creek Bridge Overflow\900 CADD\950 Drowings\Track\VCTC_SCB_G-002.dgn 2:\Engineering\VCTC\Sespe Creek Bridge Overflow\900 CADD\950 Drowings\Plot Drivers\PlotStamp.tbl 2:\Engineering\VCTC\Sespe Creek Bridge Overflow\900 CADD\950 Drowings\Plot Drivers\SCRRA-11X17-CLR-PDF-HW-CLR.pitcfg Z:\Engineering\VCTC\Sespe Creek Bridge Overflow\900 CADD\950 Drowings\Plot Drivers\SCRRA-11X17-CLR-PDF-HW-CLR.pitcfg

	TRAN	TURA COUNTY NSPORTATION MISSION
١		

SESPE CREEK OVERFLOW RAILROAD BRIDGE REPAIR ON THE SANTA PAULA BRANCH LINE, FILLMORE, CA

INDEX OF DRAWINGS

CONTRACT	NO.					
DRAWING NO.						
G-002						
REVISION	SHEET	NO.				
2 OF 31						
2 0 31						
SCALE NTO						
l	NTS		- 1			

DESIGNED BY

J. ZIEGLER

DRAWN BY

J. ZIEGLER
CHECKED BY
M. WHITE
APPROVED BY
N. ORTEGA

3-18-2025

INFORMATION CONFIDENTIAL:

All plans, drawings, specifications, and ry information creditions, and ry information continued in the service of the service of

RAILPROS
B11 VILSHIRE. SUITE 1820
LDS ANGLEES: C4 900175
WIT. RAILPROS. COM
PHONE: (213)627-0044


SUBMITTED: JULINA CORONA P.E. PROJECT MANAGER

RAILROAD CONTACT **ABBREVIATIONS** ABBREVIATIONS (CONT.) **EXISTING LINESTYLES** SIERRA NORTHERN RAILWAY DIVISION MANAGER (530) 490-1446 ADS ADVANCED DRAINAGE SYSTEMS PCC PORTLAND CEMENT CONCRETE ASPHALT SURFACE AVE PED **PEDESTRIAN** BUILDING AT&T AMERICAN TELEPHONE AND TELEGRAPH COMPANY POT HOLE PH POINT OF INTERSECTION OF TURNOUT AWW ABSOLUTE WORK WINDOW PITO BRUSH LINE/TREE LINE BLVD BOULEVARD PMT PROPOSED MAIN TRACK CONCRETE SURFACE CI CAST IRON POB POINT OF BEGINNING CENTERLINE POE POINT OF ENDING ⊈ CMPA CORRUGATED METAL PIPE ARCH POTO POWER OPERATED TURNOUT DIRT SURFACE CONT PROP PROPOSED CP CONTROL POINT PS POINT OF SWITCH FLOW LINE CPUC CALIFORNIA PUBLIC UTILITIES COMMISSION POINT OF INTERSECTION EXISTING TRACK CTC CENTER TO CENTER SPI POINT OF INTERSECTION - SPIRAL CWR CONTINUOUS WELDED RAIL FENCE AND HANDRAILS SC POINT OF SPIRAL TO CIRCULAR CURVE Dc DEGREE OF CURVE CS POINT OF CIRCULAR CURVE TO SPIRAL GUARD RAIL θs POINT OF SPIRAL TO TANGENT DEFLECTION ANGLE - SPIRAL ST DI DRAINAGE INLET TS POINT OF TANGENT TO SPIRAL DEPARTMENT OF TRANSPORTATION (U.S.) DOT PΤ POINT OF TANGENCY PROPERTY LINE DWG PTC POSITIVE TRAIN CONTROL DRAWING EΑ PVI POINT OF VERTICAL INTERSECTION RAILROAD TRACK Εa ACTUAL SUPERELEVATION PVT POINT OF VERTICAL TANGENT RETAINING WALL Eu UNBALANCED SUPERELEVATION PVC POINT OF VERTICAL CURVE ELEV, EL **ELEVATION** QWEST QWEST ENGINEERING ROAD STRIPING EMT EXISTING MAIN TRACK RADIUS TOP OF SLOPE ES ENGINEERING STANDARDS (SCRRA STANDARD DRAWINGS) RAIL BOUND MANGANESE EG RR SCRRA INTERTRACK FENCE/WWM EXISTING GROUND RAII ROAD EWD EASTWARD DIRECTION RH RIGHT HAND EXIST, EX, (E) EXISTING RCB REINFORCED CONCRETE BOX FL FLOW LINE ROW, R/W RIGHT-OF-WAY PROPOSED LINESTYLES FT FEET, FOOT RT RIGHT RAILROAD WORKER IN CHARGE FWY FRFFWAY RWIC PROPOSED TRACK GPS GLOBAL POSITIONING SYSTEM SCRRA SOUTHERN CALIFORNIA REGIONAL RAIL AUTHORITY HMA HOT MIX ASPHALT SERA, SNR SIERRA NORTHERN RAILWAY PROPOSED RESURFACE TRACK HR HOUR STA STATION HTTO HAND THROW TURNOUT ST STREET HDPE HIGH DENSITY POLY ETHYLENE SD STORM DRAIN HST HOLLOW STEEL TIE SUB SUBDIVISION ----- EXISTING SHIFT TRACK INSULATED JOINT SWT LI SWITCH JCT JUNCTION TCE TEMPORARY CONSTRUCTION EASEMENT LENGTH TF TRACK FOOT L LA LOS ANGELES TO TURNOUT - INTERTRACK FENCE/WWM LACMTA LOS ANGELES COUNTY METROPOLITAN TRANSPORTATION AUTHORITY TOR, T/R TOP OF RAIL ROADWAY GUARDRAIL LOS ANGELES COUNTY TRANSPORTATION COMMISSION LACTC TWC TIME WARNER CABLE Lc LENGTH OF CIRCULAR CURVE TYP **TYPICAL** RETAINING WALL / GRAVITY WALL LENGTH OF SPIRAL UPRR UNION PACIFIC RAILROAD Ls LF LINEAL FOOT VELOCITY $\stackrel{ extstyle }{ o}$ TOP OF SLOPE LH LEFT HAND VERT VERTICAL _________________K-RAIL WATER SURFACE ELEVATION LLT LAST LONG TIE WSE LT WSM WELDED SPRING MANGANESE PLATFORM HANDRAIL LG LIP OF GUTTER WWD WESTWARD DIRECTION LWW LIMITED WORK WINDOW WWM WELDED WIRE MESH MCI MICROWAVE COMMUNICATIONS INC. XING CROSSING ______CUT_____ CUT MFS MERCANTILE FREIGHT SERVICE —— — — — — — — — — FLOW LINE MH MANHOLE MIN MINUTE BLOCK WALL MIN MINIMIIM CENTERLINE OF ROAD **MILEPOST** MPH MILES PER HOUR GUARDRAIL MAIN TRACK NAD 83 NORTH AMERICAN DATUM OF 1983 NAD 88 NORTH AMERICAN DATUM OF 1988 — TD — TD — TRENCH DRAIN NO NUMBER NTS NOT TO SCALE OH OVERHEAD - ◆ - ◆ - ◆ - ◆ - ◆ - ◆ - PLATFORM EDGE FENCE OTM OTHER TRACK MATERIAL ---- LIMITS OF CONSTRUCTION BOUNDARY OFF OFFSET 0.0. ON CENTER CONST JOINT VIIII TERVIIII TERVIIII TERVIII TUURIII TERVIII TERVII -xx---TSF---xx----xx----xx-----xX-----XILT CONTROL FENCE ------PROPOSED TEMPORARY CONSTRUCTION EASEMENT SESPE CREEK OVERFLOW RAILROAD BRIDGE REPAIR ON THE SANTA PAULA BRANCH LINE, FILLMORE, CA ONTRACT NO. INFORMATION CONFIDENTIAL INFORMATION CONFIDENTIAL.
All plans, drawings, specifications, and or information furnished herewith shall remain the property of the Southern California Regional Rail Authority and shall be held confidential; and shall not be used for any purpose not provided for in agreements with the Southern California Regiona Rail Authority. **VENTURA COUNTY** J. ZIEGLER DRAWING NO. FINAL DESIGN (100%) **TRANSPORTATION** G-003 J. ZIEGLER CAMERA READY COMMISSION REVISION SHEET NO. M. WHITE No. C69534 3 OF 30 EXP: 06-30-26 RAILPROS STANDARD ABBREVIATIONS N. ORTEGA SCALE NTS

3-18-2025

REV DATE

JULINA CORONA, P.E PROJECT MANAGER



3-18-2025

SUBMITTED:

JULINA CORONA, P.E PROJECT MANAGER

NTS

USER - jackson.ziegler Creek Bridge Overflow/900 CORE\03 Phase 1 Final Desig Creek Bridge Overflow/900

- 2. ALL CONSTRUCTION ACTIVITIES SHALL BE SCHEDULED AND COORDINATED WITH THE ENGINEER AND THE VARIOUS COMPANIES, AGENCIES, AND OTHER CONTRACTORS WHO MAY BE AFFECTED BY THIS WORK.
- 3. HORIZONTAL AND VERTICAL CONTROL POINTS FOR THE SITE LAYOUT ARE IDENTIFIED IN THE CONTRACT DOCUMENTS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO UTILIZE THESE CONTROL POINTS TO ASSURE THAT ALL FACILITIES INCLUDED IN PROJECT ARE CONSTRUCTED AT THE CORRECT HORIZONTAL AND VERTICAL
- 4. SECTION 4216/4217 OF THE GOVERNMENT CODE REQUIRES A DIG ALERT IDENTIFICATION NUMBER BE ISSUED BEFORE A "PERMIT TO EXCAVATE" IS VALID. THI CONTRACTOR SHALL CALL THE UNDERGROUND SERVICE ALERT (1-800-422-4133) TWO (2) WORKING DAYS PRIOR TO CONSTRUCTION TO OBTAIN A DIG ALERT ID
- 5. CALIFORNIA SENATE BILL 1359 (APPROVED 2006) OUTLINES PROCEDURES FOR LOCATING UTILITIES BY HAND EXCAVATION, THE CONTRACTOR SHALL BECOME FAMILIAR WITH THIS LEGISLATION AND COMPLY WITH ITS DIRECTIVE PRIOR TO EACH CONSTRUCTION ACTIVITY WITHIN RAILROAD RIGHT-OF-WAY, THE CONTRACTOR SHALL
- 6. SIERRA NORTHERN & VCTC ARE NOT MEMBERS OF DIG ALERT. THE CONTRACTOR SHALL CALL SIERRA NORTHERN'S 24-HOUR EMERGENCY NUMBER A MINIMUM OF FIVE DAYS PRIOR TO BEGINNING CONSTRUCTION TO MARK SIGNAL AND COMMUNICATION CABLES AND CONDUITS. TO ASSURE CABLES AND CONDUITS HAVE BEEN MARKED, NO WORK MAY PROCEED UNTIL THE CONTRACTOR HAS BEEN PROVIDED WITH WRITTEN AUTHORIZATION TO PROCEED FROM SIERRA NORTHERN. IN CASE OF SIGNAL EMERGENCIES OR GRADE CROSSING PROBLEMS, THE CONTRACTOR SHALL CALL THE 24-HOUR EMERGENCY NUMBER:(888) 864-6995.
- 7. THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS FOR CONFLICTS WITH EXISTING UTILITIES, SIGNAL CABLES/EQUIPMENT, FIBER OPTIC LINES, AND/OR OTHER ITEMS THAT MIGHT IMPAIR CONSTRUCTION ACTIVITIES. INCONSISTENCIES FOUND SHALL BE REPORTED TO THE ENGINEER
- 8. REPAIRS TO THE DAMAGED MATERIALS OR FACILITIES INTENDED TO REMAIN IN PLACE SHALL BE MADE BY THE CONTRACTOR AT THE CONTRACTOR'S EXPENSE UNLESS
- 9. ALL EXCAVATED WASTE MATERIAL SHALL BE IMMEDIATELY REMOVED FROM THE SITE. ON SITE STORAGE OF EXCAVATED WASTE MATERIAL SHALL NOT BE PERMITTED AT ANY TIME.

10. DEFINITIONS

TRACK WHICH IS OUT OF SERVICE FOR A GIVEN PERIOD OF TIME. A. TRACK OUTAGE:

TRACK ON WHICH TRAINS ARE OPERATING AND INTERRUPTION OF SERVICE MAY OCCUR ONLY WITHIN AN B. ACTIVE TRACK:

APPROVED "WINDOW" AS DEFINED BELOW.

C. FOULED TRACK TRACK IS FOULED WHEN AN OBSTRUCTION IS PLACED WITHIN FOUR (4) FEET FROM THE NEAREST RAIL OF THE

TRACK OR WHEN AN OVERHEAD OBSTRUCTION IS PLACED WITHIN TWENTY-TWO AND A HALF FEET (22'-6") ABOVE THE TOP OF RAIL.

A GIVEN PERIOD OF TIME BETWEEN OPERATING TRAINS WHERE A TRACK MAY BE FOULED WITH THE STIPULATION THAT THE TRACK SHALL BE BACK IN SERVICE AT THE END OF THE GIVEN PERIOD OF TIME. A FORM OF POSITIVE PROTECTION SHALL ALSO BE REQUIRED. D. WINDOW

E. EXCLUSIVE TRACK WINDOW / ABSOLUTE WORK WINDOW (AWW):

AN APPROVED WORK WINDOW IN WHICH NO TRAIN MOVEMENTS WILL OPERATE ON ANY TRACK WITHIN THE WINDOW LIMITS. THE CONTRACTOR MAY DISMANTLE, REMOVE, RECONSTRUCT, OR OTHERWISE OBSTRUCT TRACKS WITHIN THE LIMITS OF SUCH A WINDOW THIS WORK WAY BE PROTECTED BY TRACK OUT OF SERVICE, TRACK AND TIME LIMITS, OR BY FORM B TRACK BULLETIN

F. LIMITED TRACK WINDOW / LIMITED WORK WINDOW (LWW):

AN APPROVED WORK WINDOW FOR SOME, BUT NOT ALL TRACKS WITHIN A GENERAL WORK AREA (E.G. ONE TRACK REMAINS FOR OPERATION OF TRAINS, OTHER TRACKS ARE AVAILABLE FOR THE CONTRACTOR'S WORK), MOVEMENT OF TRAINS OVER THE TRACK(S) OF A LIMITED TRACK WINDOW IS UNDER THE CONTROL OF THE SIERRA NORTHERN EMPLOYEE-IN CHARGE (CIC) WHO WILL NOT AUTHORIZE TRAIN MOVEMENT UNLESS AND UNTIL THE CONTRACTOR PERSONNEL AND EQUIPMENT ARE CLEAR OF THE OPERATING TRACK. THE CONTRACTOR MAY REMOVE, CONSTRUCT, OR OBSTRUCT ONLY THE TRACK DESIGNATED BY THE SSWP AND MUST ARRANGE THE WORK SO THAT TRAINS CAN OPERATE WITHOUT DELAY ON THE REMAINING TRACK(S) IN THE WORK AREA. THIS WORK MAY BE PROTECTED BY TRACK OUT OF SERVICE, TRACK AND TIME, OR BY FORM B TRACK BULLETIN.

G. WORK WINDOW:

AN APPROVED WORK WINDOW IN WHICH PASSENGER, FREIGHT AND ALL OTHER TRAINS AND ON-TRACK EQUIPMENT MOVEMENTS CAN BE PROHIBITED FROM ENTERING THE DEFINED LIMITS OF A SEGMENT OF TRACK. THE "FORM B" WORK WINDOW DOES NOT ALLOW THE CONTRACTOR TO REMOVE FROM SERVICE OR MODIFY THE TRACKS, SIGNALS. BRIDGES, STATIONS OR OTHER ELEMENTS OF THE OPERATING SYSTEM IN A MANNER, WHICH WILL DELAY OR IN ANY WAY AFFECT THE SAFE OPERATION OF THE TRAINS. THE "FORM B" WORK WINDOW ALLOWS THE CONTRACTOR THE ABILITY TO ENTER THE OPERATING ENVELOPE AND PERFORM CONSTRUCTION ACTIVITIES SUBJECT TO THE CONDITIONS ABOVE. AN EIC/FLAGMAN FROM SIERRA NORTHERN WILL EXERCISE STRICT CONTROL OVER THE CONTRACTOR'S CONSTRUCTION ACTIVITIES IN CONJUNCTION WITH ROADWAY WORKER PROTECTION REGUIREMENTS TO ASSIBE THAT THE CONTRACTOR'S ACTIVITIES DO NOT DELAY OR IMPACT PROTECTION REQUIREMENTS, TO ASSURE THAT THE CONTRACTOR'S ACTIVITIES DO NOT DELAY OR IMPACT

AN APPROVED WORK WINDOW IN WHICH THE SIERRA NORTHERN RAILWAY DISPATCHER WILL AUTHORIZE MEN AND EQUIPMENT TO OCCUPY A TRACK OR TRACKS WITHIN LIMITS FOR A CERTAIN TIME PERIOD. THE DISPATCHER AUTHORITY SHALL INCLUDE AUTHORITY NUMBER, TRACK DESIGNATION, LIMITS AND TIME. MOVEMENTS MAY BE MADE IN EITHER DIRECTION WITHIN THE SPECIFIED LIMITS UNTIL THE LIMITED ARE RELEASED. H. TRACK AND TIME:

11. PRIOR TO COMMENCING WORK, ALL EXISTING SITE CONDITIONS SHALL BE FIELD VERIFIED BY THE CONTRACTOR WITH THE ENGINEER TO ASCERTAIN THE LIMITS OF WORK ACTIVITIES. THE CONTRACTOR SHALL SUBMIT AND RECEIVE THE ENGINEER'S APPROVAL OF THE PROJECT SCHEDULE AND OPERATIONS PLAN. EACH ITEM OF WORK SHALL BE DESCRIBED AND ACCOUNTED FOR IN THE CONTRACT DOCUMENTS. THE CONTRACTOR SHALL REFER TO THE SPECIFICATIONS FOR FURTHER INFORMATION REGARDING SUBMITTAL REQUIREMENTS

BY SUB APP.

GENERAL NOTES (CONTNUED)

- 12. WORK AFFECTING THE MOVEMENT OF TRAINS WILL BE UNDER THE AUTHORITY AND OVERALL CONTROL OF THE ENGINEER OR HIS
- 13. THE CONTRACTOR SHALL NOT PLACE MATERIAL AND/OR EQUIPMENT WITHIN TWENTY (20) FEET OF AN ACTIVE TRACK AT ANY TIME WITHOUT PRIOR APPROVAL FROM SIERRA NORTHERN RAILWAY.
- 14. WALKWAYS SHALL BE PLACED AS REQUIRED BY CALIFORNIA PUBLIC UTILITIES COMMISSION GENERAL ORDER NO. 118 AND 26D AND SCRRA ENGINEERING STANDARD ES2109 FOR ALL NEW CONSTRUCTION, UNLESS OTHERWISE NOTED.
- 15. THE CONTRACTOR AGREES THAT IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR WILL BE REQUIRED TO ASSUME SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY, THAT THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT LIMITED TO NORMAL WORKING HOURS, AND THE CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY HOLD SIERRA NORTHERN, VCTC, VENTURA COUNTY AND THE DESIGN PROFESSIONAL HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF ALLEGED OF ALLEGED OF ALLEGED, IN CONNECTION WITH THE PERFORMANCE
- 16. THE LOCATIONS AND DIMENSIONS SHOWN ON THE PLANS FOR EXISTING FACILITIES ARE IN ACCORDANCE WITH AVAILABLE INFORMATION WITHOUT UNCOVERING AND MEASURING. THE ENGINEER DOES NOT GUARANTEE THE ACCURACY OF THIS INFORMATION OR THAT ALL EXISTING
- 17. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE APPLICABLE CODES, ORDINANCES, AND STANDARD SPECIFICATIONS OF ALL AGENCIES THAT HAVE THE RESPONSIBILITY OF REVIEWING PLANS AND SPECIFICATIONS FOR CONSTRUCTION OF ALL ITEMS PER THESE PLANS AND SPECIFICATIONS IN THIS LOCALITY.
- 18. THE CONTRACTOR SHALL OBTAIN ALL THE NECESSARY PERMITS AND PAY PERMIT FEES AS REQUIRED FOR CONSTRUCTION OF THIS PROJECT.
- 19. THE CONTRACTOR SHALL CLEAN UP ALL DEBRIS AND MATERIALS RESULTING FROM HIS OPERATION AND RESTORE ALL SURFACES, STRUCTURES, DITCHES, AND PROPERTY TO THE SATISFACTION OF THE ENGINEER.
- 20. ONCE IN SERVICE, CONTRACTOR SHALL PROVIDE FOR THE CONTINUOUS OPERATION OF THE EXISTING FACILITY WITHOUT INTERRUPTION DURING CONSTRUCTION EXCEPT DURING EXCLUSIVE TRACK WINDOWS OUTLINED IN THE SPECIFICATIONS AND UNLESS SPECIFICALLY AUTHORIZED
- 21. CONTRACTOR TO IDENTIFY DEPTH AND LOCATION OF ALL EXISTING UNDERGROUND UTILITIES. FOR LOCATION OF SIGNALS AND COMMUNICATION CONDUITS CONTACT RAILROAD SIGNAL DEPARTMENT.
- 22. TIMBER TIES SHALL BE SPACED AT 19 1/2 INCHES ON CENTER.
- 23. TEMPORARY FACILITIES CONSTRUCTED AND REMOVED BY THE CONTRACTOR TO PROVIDE FOR MAINTENANCE RAIL OPERATIONS DURING THE PHASING OF CONSTRUCTION (SUCH AS PLACEMENT OF A TEMPORARY TRACK PANEL AT THE LOCATION OF A TURNOUT TO BE CONSTRUCTED AT A FUTURE PHASE) WILL BE CONSIDERED INCIDENTAL TO OTHER ITEMS BEING CONSTRUCTED. NO SEPARATE MEASUREMENT OR PAYMENT WILL BE MADE FOR PROVIDING FOR THE CONTINUOUS OPERATION OF RAIL TRAFFIC.
- 24. EXISTING RAILROAD SIGNAGE (INCLUDING SPEED SIGNS) SHALL BE MAINTAINED DURING CONSTRUCTION PERIOD. ALL RAILROAD SIGNAGE SHALL BE FULLY RESTORED UPON COMPLETION OF EACH WORK PERIOD IN ACCORDANCE WITH SCRRA ENGINEERING STANDARDS. PRIOR TO CONSTRUCTION, SCRRA STANDARD PROJECT, NOTICE SIGNS SHALL BE PLACED AT LOCATIONS AS DIRECTED BY THE ENGINEER. NO TRESPASSING SIGNS SHALL BE PLACED IN ACCORDANCE WITH ES5214 AND AS SHOWN ON THE DRAWINGS.
- 25. CONTACT SIERRA NORTHERN RAILWAY TO ARRANGE FOR FLAGGING SERVICES. FLAGGING SERVICE IS DEPENDENT ON THE EIC AVAILABILITY AND MAY REQUIRE A MINIMUM OF FIFTEEN WORKING DAYS PRIOR TO BEGINNING WORK. PRIOR NOTIFICATION OF FLAGGING SERVICES DOES NOT GUARANTEE THE AVAILABILITY OF THE EIC FOR THE PROPOSED DATE OF WORK.
- 26. ALL PERSONNEL TO ACCESS SPBL ROW MUST COMPLY WITH AN ACCEPTED 49 CFR PART 214 & 243 PROGRAM. CONTRACTOR TO PERFORM WORK IS RESPONSIBLE FOR ALL TESTING REQUIRED PER THEIR ACCEPTED PROGRAM. THE CONTRACTORS RWIC MUST BE CERTIFIED WITH SNR'S CONTRACTOR SAFETY CERTIFICATION. ALLOW 5 WORKING DAYS FROM THE REQUEST TO SNR FOR SAFETY TRAINING TO BE ARRANGED.
- 27. NO MECHANIZED EXCAVATION WITHIN 2 FEET OF FIBER LINE IS ALLOWED. QWEST, VCTC AND MFS TO BE PRESENT FOR ANY ACTIVITY WITHIN 5 FEET HORIZONTALLY OR VERTICALLY OF FIBER LINES. NO FACILITIES MAY BE ADDED CLOSER THAN 2 FEET VERTICALLY OR HORIZONTALLY TO QWEST, LACTC AND MFS'S STRUCTURES, INCLUDING THE ENCASEMENT. CONTRACTOR SHALL POTHOLE ALL FIBER LINES WITHIN THE WORK LIMITS BEFORE BEGINNING WORK IN THAT VICINITY IF CONSTRUCTION EQUIPMENT INTENDS TO DRIVE OVER THE FIBER LINE, CONTRACTOR SHALL PLACE STEEL PLATES OVER THE FIBER LINE BEFORE CONSTRUCTION CREWS DRIVE OVER FIBER.

DESIGN CRITERIA

SCRRA DESIGN CRITERIA MANUAL, MARCH 2024

PROJECT SPECIFIC SPECIFICATIONS

SCRRA STANDARD SPECIFICATIONS

FINAL DESIGN (100%) CAMERA READY

INFORMATION CONFIDENTIAL INFORMATION CONFIDENTIAL.
All plans, drawings, specifications, and or information furnished herewith shall remain the property of the Southern California Regional Rail Authority and shall be held confidential; and shall not be used for any purpose not provided for in agreements with the Southern California Regiona Rail Authority.

J. ZIEGLER

J. ZIEGLER

N. ORTEGA

3-18-2025

M. WHITE











CONTRACT	NO.		
DRAWING 1	١٥.		
	G-00	5	
REVISION	SHEET	NO.	
	5	OF	30
SCALE	NTS	;	



	PROJECT CONTROL						
POINT NUMBER	NORTHING	EASTING	ELEVATION	DESCRIPTION			
500	1971511.827	6280526.913	457.84'	CUT X IN CONC ON WB SIDE OF BRIDGE 27' EAST OF WEST EXPANSION JOINT			
501	1971316.983	6280828.833	458.67'	CUT X IN CONC ON WB SIDE OF BRIDGE 94' WEST OF EAST EXPANSION JOINT			
502	1971336.612	6280917.852	446.28'	3.5" USC&GS BRASS BM DISK STAMPED "S121B8, 1971" ON SE ABUTMENT, CONC WALKWAY			
503	1971201.537	6281085.270	458.32'	MAGNAIL & SPIKE IN GROUND 5.15' FROM CONC CURBING AT GATE TO RR ABUTMENT ON SE SIDE OF RR TRX			
-							

LEGEND:

A PROJECT CONTROL POINT

BASIS OF COORDINATES:

THE BASIS OF HORIZONTAL CONTROL IS THE NORTH AMERICAN DATUM OF 1983, 2011 ADJUSTMENT (NAD83-2011), MUTI-YEAR CORS SOLUTION 2 (MYSC2) ESTABLISHED BY USING THE SMARTNET SYSTEM OF CONTINUOUSLY OPERATING REFERENCE STATIONS (CORS).

COORDINATES ARE IN CALIFORNIA STATE PLANE COORDINATE SYSTEM, ZONE 5, EPOCH 2023.25, US SURVEY FT.

VERTICAL SURVEY CONTROL VALUES HEREON ARE BASED UPON THE NORTH AMERICAN VERTICAL DATUM OF 1988, GNSS-DERIVED BY FAST STATIC SURVEY METHODS USING GEOID18 PER CALIFORNIA PUBBLIC RESOURCES CODE 8890, DEFINED AS CALIFORNIA ORTHOMETRIC HEIGHTS

ALL POSITIONS ARE CALCULATED PER A FULLY CONSTRAINED LEAST SQUARES ADJUSTMENT USING STARNET V11 LEAST SQUARES ADJUSTMENT SOFTWARE.

GRAPHIC SCALE

DESIGNED BY M. CUSICK INFORMATION CONFIDENTIAL **VENTURA COUNTY** All plans, drawings, specifications, and o M. CUSICK TRANSPORTATION COMMISSION CODY J FESTA C. FESTA

03-18-2025

SESPE CREEK OVERFLOW BRIDGE REPAIR ON THE SANTA PAULA BRANCH LINE, FILLMORE,

SURVEY CONTROL EXHIBIT

**************************************	10.040.000.0000				
CONTRACT	NO.				
DRAWING N	١٥.				
G-006					
REVISION	SHEET	NO.			
	6	OF	30		
SCALE AS S	SHOW	'N			
	CONTRACT DRAWING N (REVISION	REVISION SHEET 6	CONTRACT NO. DRAWING NO. G-006 REVISION SHEET NO. 6 OF		

REV. DATE


FINAL DESIGN (100%) CAMERA READY







- CONTRACTOR TO REMOVE AND REPLACE TRACK FOR BRIDGE CONSTRUCTION.
- CONTRACTOR SHALL MAINTAIN A MINIMUM WALKWAY PER SCRRA ES 2109 FOR ALL REINSTALLED AND RESURFACED TRACK.
- 3. SEE STRUCTURAL PLANS FOR PROPOSED BRIDGE.
- CONTRACTOR SHALL GRADE FOR BOTH DITCHES TO PROPERLY DRAIN.
- CONTRACTOR TO BENCH FILL INTO EXISTING GRADE WITH A MAX OF 3' HORIZONTAL BENCH FOR LOWEST BENCH, 2' MAX ON SUBSEQUENT



INFORMATION CONFIDENTIAL: All plans, drawings, specifi-cations, and or information furnished herewith shall remain the property of the the Southern California Regional Rail authority and shall be held confidential: and shall not be used for ony purpose not provided for in agreements with the Southern California Regional Rail Authority. FINAL DESIGN (100%) NOT FOR CONSTRUCTION REV. DATE

J. ZIEGLER J. ZIEGLER M. WHITE N. ORTEGA 3-18-2025







JULINA CORONA, P.E. PROJECT MANAGER


SESPE CREEK OVERFLOW RAILROAD BRIDGE REPAIR ON THE SANTA PAULA BRANCH LINE, FILLMORE, CA TYPICAL SECTION

CONTRACT	NO			
CONTRACT DRAWING N				
TD-001				
REVISION	SHEET 7	NO. OF	30	
SCALE	NTS	3		

3/21/2025 3:09:36 PM USER - jackson.ziegler Z:\tenspecifica\tenspecifi









12-25-2023

JULINA R. CORONA, P.E. PROJECT MANAGER



TYPICAL SECTION - EXISTING BENTS SCALE: 1/4" = 1'-0"



TYPICAL SECTION - NEW BENTS 2 & 3 SCALE: 1/4" = 1'-0"

×	DEPTH	TOP/RAIL TO TOP/DECK
	8" 8" 8" 4"	RAIL & TIE PLATE TIMBER TIE MINIMUM BALLAST MAXIMUM HMA AT CENTERLINE AND VARIES WITH 17. CROSS SLOPE
2	2'-4"	TOTAL (SEE NOTE 2)


KEYNOTES

- 1) RAIL AND TIMBER TIES
- 2) PRECAST CONCRETE BALLAST CURB & SIDEWALK
- PRECAST PRESTRESSED CONCRETE DOUBLE BOX GIRDER
- 4) CONCRETE SHEAR KEY
- (5) CAST-IN-PLACE CONCRETE BENT CAP
- (6) CONCRETE COLUMN, 4'-0"Ø
- (7) CIDH CONCRETE PILE, 6'-0"Ø
- (8) HANDRAIL
- 9 BEARING PAD
- (10) CONCRETE IN-FILL WALL
- (11) EXISTING GRADE
- (12) EXISTING RAIL AND TIES
- (13) EXISTING BALLAST CURB & SIDEWALK
- EXISTING PRECAST PRESTRESSED CONCRETE DOUBLE BOX GIRDER
- (15) EXISTING STEEL ANGLE
- (16) EXISTING CONCRETE BENT CAP
- (17) EXISTING STEEL PILE
- (18) EXISTING CONCRETE BRACE
- (19) EXISTING HANDRAIL
- (20) EXISTING BEARING PAD, 3/4" ± THK
- (21) EXISTING CONCRETE IN-FILL WALL
- 2~4" ID GALVANIZED METAL CONDUIT WITH CONDUIT BRACKET EACH SIDE OF BRIDGE STRUCTURE (TOTAL 4) PER SCRRA STANDRAD PLAN ES6001-05 & ES6002-14
- (23) BALLAST
- (24) HOT MIX ASPHALT (HMA)

NOTES

- ALL EXISTING DIMENSIONS ARE APPROXIMATE AND SHALL BE FIELD MEASURED AND CONFIRMED BEFORE START OF WORK OR ORDERING MATERIALS MATERIALS.
- DIMENSIONS LISTED ARE MINIMUM AND SHALL BE ADJUSTED AS NEEDED TO MAINTAIN THE EXISTING TRACK PROFILE.
- REFER TO SCRRA ENGINEERING STANDARD DRAWING ES 6001-02 FOR BALLAST DEPTH AND HMA DEPTH REQUIREMENTS.
 - REFER TO SCRRA ENGINEERING STANDARD DRAWING ES 6001-03 FOR HMA PLACEMENT REQUIREMENTS.













SESPE CREEK OVERFLOW BRIDGE REPAIR ON THE SANTA PAULA BRANCH LINE, FILLMORE, CA


GENERAL PLAN NO. 2



CAMERA READY

3/22/25 UPDATED GEN NOTES, SHEET NUMBERS

REV. DATE



G. ESTEPA

PROVED BY
M. SARWAR

12-25-2023

HECKED BY

the ventura County
- Transportation Commission
and shall be held confidential
and shall not be used for
any purpose not provided
for in agreements with the
Ventura Country
- Transportation Commission.

INDEX OF DRAWINGS:

SHT.	DWG. NO.	REV. NO.	TITLE
∆ (10 \	S-001		GENERAL PLAN NO. 1
∑ 11 3	S-002		GENERAL PLAN NO. 2
12	S-003		GENERAL NOTES AND INDEX OF DRAWINGS
\$ 13 \$	S-004		STAGE CONSTRUCTION PLAN
\ 14 \	S-005		FOUNDATION PLAN
\ 15 \	S-006		ABUTMENT DETAILS NO. 1
5 16 3	S-007		ABUTMENT DETAILS NO. 2
\ 17 \	S-008		ROCK SLOPE PROTECTION
\ 18 \	S-009		BENT DETAILS NO. 1
5 19 3	S-010		BENT DETAILS NO. 2
20 3	S-011		BENT DETAILS NO. 3
21 3	S-012		GIRDER DETAILS NO. 1
223	S-013		GIRDER DETAILS NO. 2
23 3	S-014		HANDRAIL REPLACEMENT PLAN
24	S-015		HANDRAIL DETAILS
25 }	S-016		MISCELLANEOUS DETAILS NO. 1
\\\ 26 \\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	S-017	~~~	MISCELLANEOUS DETAILS NO. 2
27	GE-001		LOG OF TEST BORINGS
28	GE-002		SOIL LEGEND 1 OF 2 - LOG OF TEST BORINGS
29	GE-003		SOIL LEGEND 2 OF 2 - LOG OF TEST BORINGS
30	SC-001		ROCK SLOPE PROTECTION, MANDATORY OWNER OPTION

CONSTRUCTION NOTE:

CONTRACTOR SHALL FIELD VERIFY AND CALCULATE THE SEAT ELEVATIONS FOR THE NEW ABUTMENT AND BENTS TO MAINTAIN THE TRACK PROFILE BEFORE FABRICATION OR ORDERING ANY MATERIALS.

SESPE CREEK OVERFLOW BRIDGE REPAIR ON THE SANTA PAULA BRANCH LINE, FILLMORE, CA


GENERAL NOTES AND INDEX OF DRAWINGS


COMMISSION


SUBMITTED:

JULINA R. CORONA, P.E. PROJECT MANAGER

RAILPROS







BENT 2

ABUT 1

PLAN ABUT 1 BENT 2 ELEVATION

CONSTRUCTION STAGE 3 - FINAL

NOTES - STAGE 3, FINAL:

BENT 6

- RE-INSTALL SPAN 4 SUPERSTRUCTURE INCLUDING GIRDERS, WALKWAYS & HANDRAILS
- BUILD ROCK SLOPE PROTECTION FOR ABUTMENT 1
- INSTALL NEW SUPERSTRUCTURE ON SPANS 1 AND 2 INCLUDING WALKWAYS AND HANDRAILS
- INSTALL STEEL PLATES, GIRDER RESTRAINERS, HMA, BALLAST, TRACKS & TIES



VENTURA COUNTY TRANSPORTATION COMMISSION RAILPROS



SESPE CREEK OVERFLOW BRIDGE REPAIR ON THE SANTA PAULA BRANCH LINE, FILLMORE, CA

STAGE CONSTRUCTION PLAN

CONTRACT NO. DRAWING NO. S-004 REVISION SHEET NO. 13 OF 30 NO SCALE


PM USER • gerry.estepo fs\ZZPfanieering\VCTC\Sespe Creek Bridge Overflow\900 CADD\950 Drawings\Structures\` configuration\WorkSpaces\SCRRA-Structures\Standords\Tables\Pen\PlotStamp-HalfSize.tbl andord \All Aqency\\MetroLink-SCRRA\Work\Space\Standords\Pltcfg\pdf.pl

3/22/25 UPDATED NOMENCLATURE, STAGE CONSTRUCTION NOTES, EG & RSP PROFILE REV. DATE

H. YANG PROVED BY M. SARWAR 12-25-2023







				PILE DATA	A TABLE		
	0115 71105	NOMINAL RESIS	TANCE (kips)	PILE CUT-OFF	DESIGN TIP	SPECIFIED TIP	NOMINAL DRIVING
LOCATION	PILE TYPE	COMPRESSION	TENSION	ELEVATION (ft)	ELEVATION (ft)		RESISTANCE (kips)
ABUT 1	72″Ø CIDH	716	0	420.75	(a) 322.25 (c) 378.25 (d) 355.75	322.25	N/A
BENT 2	72"Ø CIDH	778	304	425.00	(a) 350.0 (b) 392.0 (c) 364.0 (d) 355.0	350.00	N/A
BENT 3	72″Ø CIDH	778	304	429.00	(a) 354.0 (b) 396.0 (c) 368.0 (d) 359.0	354.00	N/A

NOTES:
1. DESIGN TIP ELEVATIONS ARE CONTROLLED BY: (a) COMPRESSION. (b) TENSION. (c) SETTLEMENT. AND (d) LATERAL LOAD.
2. THE SPECIFIED TIP ELEVATION FOR DRIVEN PILES MUST NOT BE RAISED ABOVE THE DESIGN TIP ELEVATIONS FOR SETTLEMENT AND LATERAL LOAD. THE SPECIFIED TIP ELEVATION FOR CIDH PILES MUST NOT BE RAISED.

		BENCH	MARK	
POINT NUMBER	NORTHING	EASTING	ELEV (FT)	DESCRIPTION
500	1971511.827	6280526.913	457.84′	CUT X CONC ON WB SIDE OF BRIDGE 27' EAST OF WEST EXP JT
501	1971316.983	62808728.833	458.67′	CUT X CONC ON WB SIDE OF BRIDGE 94' EAST OF WEST EXP JT
502	1971336.612	6280917.852	446.28′	3.5" USC&GS BRASS BM DISK STAMPED "S12188, 1971" ON SE ABUTMENT, CONC WALKWAY
503	1971201.537	6281085.270	458.32′	MAGNAIL & SPIKE IN GROUND 5.15' FROM CONC CURBING AT GATE TO RR ABUTMENT DN SESIDE OF RR TRACK

SURVEY CONTROL:

THE BASIC HORIZONTAL CONTROL IS THE NORTH AMERICAN DATUM OF 1983, 2011 ADJUSTMENT (NAD83-2011), MUTI-YEAR CORS SOLUTION 2 (MYSC2) ESTABLISHED BY USING THE SMARTNET SYSTEM OF CONTINUOUSLY OPERATING REFERENCE STATIONS (CORS).

COORDINATES ARE IN CALIFORNIA STATE PLAN COORDINATE SYSTEM, ZONE 5, EPOCH 2023.25, US

VERTICAL SURVEY CONTROL VALUES HEREON ARE BASED UPON THE NORTH AMERICAN YERICAL DATUM OF 1988, GNSS-DERIVED BY FAST STATIC SURVEY METHODS USING GEIOD18 PER CALIFORNIA PUBLIC RESOURCES CODE 8890, DEFINED AS CALIFORNIA ORTHOMETRIC HEIGHTS OF 1988 (CH88).

ALL POSITION ARE CALCULATED PER A FULLY CONSTRAINED LEAST SQUARES ADJUSTMENT USING STARNET V11 LEAST SQUARES ADJUSTMENT SOFTWARE.

JULINA R. CORONA, P.E. PROJECT MANAGER

HYDRAULOGICAL DATA

50 YEAR FLOOD LEVEL = 448.45 100 YEAR FLOOD LEVEL = 452.18

LEGEND

--- NEW STRUCTURE

72" Ø CIDH PILE

XXX.X BOTTOM OF PILE CAP ELEVATION

DIRECTION OF FLOW

NOTES

ONLY NEW STRUCTURE SHOWN FOR CLARITY EXISTING STRUCTURE PORTION THAT REMAINS IN PLACE IS NOT SHOWN. SEE GENERAL PLAN AND STAGE CONSTRUCTION



THIS STAMP CERTIFICATION IS LIMITED TO MODIFICATIONS ONLY WITH REVISION SYMBOL SHOWN

		FINAL DESIGN (100%) CAMERA READY			INFORMATION CONFIDENTIAL: All plans, drawings, specifications, and or information furnished herewith shall remain the property of the Ventura County	DR
		_			Transportation Commission and shall be held confidential:	СН
					and shall not be used for any purpose not provided for in agreements with the	AP
Δ	3/22/25	UPDATED CONTOURS, ABUT 1 SHEAR KEY LINES, SPELLING			Ventura Country	DA
REV.	DATE		BY SUB.	APP.	Transportation Commission.	

SIGNED BY H. KAZEM	PROFESSIONA
AWN BY G. ESTEPA	SEL STUMING WASE
ECKED BY H. YANG	Shamed Razem W. No. C90676
PROVED BY M. SARWAR	EXP: 12-31-25
TE 12-25-2023	FOF CALIFO








SESPE CREEK OVERFLOW BRIDGE REPAIR ON THE SANTA PAULA BRANCH LINE, FILLMORE, CA


	CONTRACT	NO.			_
۸	DRAWING 1	١٥.			_
Α		S-00	5		
	REVISION	SHEET	NO.		_
		14	OF	30	
	SCALE	AS SHO	\WKI		
		AS SH	JWIN		


FOUNDATION PLAN











NOTES:

- 1. ALL HOOPS ARE ULTIMATE BUTT SPLICES
- FOR PILE TIP AND CUT-OFF ELEVATION, SEE PILE DATA TABLE ON "FOUNDATION PLAN" SHEET
- 3. NO SPLICES ALLOWED IN THE COLUMN MAIN REINFORCEMENT
- 4. SPLICES SHALL BE SERVICE SPLICES "MECHANICAL COUPLERS"

5. REFER TO PROJECT SPECIFICATIONS FOR PILE AND COLUMN CONSTRUCTION IN WET CONDITIONS.

LEGEND



AL: DESIGNED BY
H. KAZEM

DRAWN BY
T. KORPRASERTSUD

CHECKED BY
H. YANG
APPROVED BY
M. SARWAR

DATE
12-25-2023






VENTURA COUNTY
TRANSPORTATION
COMMISSION




SESPE CREEK OVERFLOW BRIDGE REPAIR ON THE SANTA PAULA BRANCH LINE, FILLMORE, CA

BENT DETAILS NO. 2

	CONTRACT	NO.			
	DRAWING 1	١٥.			
1		S-01	0		
	REVISION	SHEET	NO.		
		19	OF	30	
	SCALE				
		AS SHO	NWC		





THE COMPRESSIVE STRENGTH OF THE CONCRETE SHALL BE 6,500 PSI AT THE TRANSFER OF THE PRESTRESSING FORCE AND

MINIMUM COMPRESSIVE STRENGTH OF CURB CONCRETE SHALL BE 4,000 PSI AT 28 DAYS.

AIR ENTRAINING AGENTS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CURRENT EDITION OF ASTM C260. THE TOTAL ENTRAINED AIR CONTENT SHALL BE 6% +/- 1% BY VOLUME OF THE PLASTIC CONCRETE.

CONCRETE AGGREGATE SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN THE CURRENT EDITION OF ASTM C33. COARSE AGGREGATE SHALL BE SIZE NO. 67.

PRESTRESSING STRAND:

PRESTRESSING STRAND SHALL BE 0.6 INCH DIAMETER, SEVEN WIRE, UNCOATED, LOW RELAXATION PRESTRESSING STRAND WHICH IS IN ACCORDANCE WITH THE REQUIREMENTS SPECIFIED IN ASTM A416. THE PRESTRESSING STRAND SHALL HAVE AN ULTIMATE TENSILE STRENGTH OF 270 KSI. THE INITIAL PRESTRESS SHALL BE 43,400 LBS. PER PRESTRESSING STRAND UNLESS NOTED OTHERWISE.

PRESTRESSING STRAND SHALL BE TESTED IN ACCORDANCE WITH PCIRECOMMENDATIONS (MOUSTAFA METHOD) AND CERTIFIED BY THE FABRICATOR AS HAVING ADEQUATE BOND CHARACTERISTICS TO SATISFY THE PREDICTION EQUATIONS FOR TRANSFER AND DEVELOPMENT

AN ALTERNATE PRESTRESSING STRAND PATTERN WHICH HAS THE SAME ECCENTRICITY AS THE PATTERN SHOWN ON THIS PLAN AND IS BETTER SUITED TO THE MANUFACTURER'S FACILITIES WILL BE CONSIDERED. MANUFACTURER MUST SUBMIT PLANS AND COMPUTATIONS FOR ENGINEER'S APPROVAL PRIOR TO CASTING.

REINFORCING STEEL:

REINFORCING STEEL SHALL BE DEFORMED, PER CURRENT ASTM A615 SPECIFICATION AND MEET GRADE 60 REQUIREMENTS, EXCEPT BARS CROSSING CURB JOINT TO BE PER CURRENT ASTM A1035 SPECIFICATION. BARS REQUIRED TO MEET ASTM A1035 ARE NOTED IN THE

FABRICATION OF REINFORCING STEEL SHALL BE PER CHAPTER 7 OF THE CRSIMANUAL OF STANDARD PRACTICE. DIMENSIONS OF BENDING DETAILS ARE OUT TO OUT OF BAR

REINFORCING STEEL IS TO BE BLOCKED TO PROPER LOCATION AND SECURELY WIRED AGAINST DISPLACEMENT. USE PLASTIC PROTECTED REINFORCING SUPPORTS, MEETING CRSISPECIFICATIONS CHAPTER 3, CLASS 1. TACK WELDING OF REINFORCING IS PROHIBITED. MINIMUM CONCRETE COVER ON REINFORCEMENT SHALL MEET CURRENT AREMA REQUIREMENTS.

DEAD LOAD (ASSUMED - LB. PER LIN. FT. OF TRACK):

TOTAL	8,445
CURB, WALK, & HANDRAIL GIRDERS	580 3,600
BALLAST	4,065
TRACK, FASTENERS, ETC.	200

THE FABRICATOR SHALL CAMBER THE GIRDERS AS REQUIRED TO RESULT IN A NET VERTICAL DEFLECTION OF 0" DUE TO MAXIMUM DEAD LOADS SHOWN BELOW.

DEAD LOAD (ASSUMED - LB. PER LIN. FT. OF ONE GIRDER):

TRACK, FASTENERS, ETC.	100
BALLAST	2,035
CURB, WALK, & HANDRAIL	290
GIRDERS	1,800
TOTAL	4.225

LIVE LOAD: COOPER E80

IMPACT: $\frac{225}{\sqrt{g}}$ % (WHERE & = L - 24")

MANUF ACTURE

PRODUCTION PROCEDURES AND DIMENSIONAL TOLERANCES FOR THE MANUFACTURE OF PRECAST, PRESTRESSED GIRDERS SHALL BE IN ACCORDANCE WITH THE AREMA MANUAL FOR RAILWAY ENGINEERING AND THE PRECAST CONCRETE INSTITUTE'S CURRENT MANUAL MNL 116 FOR QUALITY CONTROL.

TOLERANCE FOR LOCATION OF LIFTING LOOPS SHALL BE +/- 1/2 ".

THE ENDS OF THE PRESTRESSING STRANDS SHALL BE RECESSED AND GROUTED TO A MINIMUM COVER OF 2" AFTER CASTING IS COMPLETE.

CURB SHALL BE CAST AFTER GIRDER IS REMOVED FROM FORM. GIRDERS SHALL BE SUPPLIED WITH CURB.

CONCRETE BONDING AGENT: REFER TO SPECIFICATIONS.

SURFACES SHALL BE FORMED IN A MANNER WHICH WILL PRODUCE A SMOOTH AND UNIFORM APPEARANCE WITHOUT RUBBING OR PLASTERING. UNLESS OTHERWISE NOTED, EXPOSED EDGES OF 90-DEGREES OR LESS ARE TO BE CHAMFERED 3/4 "x 3/4 ". UNFORMED SURFACES SHALL HAVE A SMOOTH FINISH FREE OF ALL FLOAT AND TROWEL MARKS.

THE FABRICATOR SHALL STENCIL THE FABRICATOR'S NAME, DATE OF FABRICATION, PIECE MARK, AND ACTUAL LIFTING WEIGHT

VOID DIMENSIONS SHOWN ARE MAXIMUM AND MUST NOT BE EXCEEDED AT ANY POINT INCLUDING SPLICES OF VOID FORM.

GIRDERS SHALL BE SUPPORTED BY BLOCKING WITHIN 1'-6" OF ENDS DURING STORAGE AND TRANSPORT. STORE AND TRANSPORT

INSPECTION, LOADING, AND SECURING FOR SHIPMENT: REFER TO SPECIFICATIONS.


LIFTING LOOPS

THE AREA AROUND LIFTING LOOPS SHALL NOT BE RECESSED. LIFTING LOOPS TO BE REMOVED IN FIELD FLUSH WITH CONCRETE SURFACE.

IF LIFTED WITH SLINGS INSTEAD OF LIFTING LOOPS, SLINGS MUST NOT BE PLACED MORE THAN 3'-0" FROM ENDS OF GIRDERS.

FABRICATOR IS RESPONSIBLE FOR DEVELOPING LIFTING LOOP ANCHORAGE DETAIL TO PROVIDE SAFETY FACTOR OF 4 ON WORKING LOAD. DETAIL SHALL BE PROOF-TESTED WITH TEST RESULTS KEPT ON FILE BY FABRICATOR AND AVAILABLE FOR INSPECTION BY THE ENGINEER.

REFER TO PROJECT SPECIFIC SPECIFICATION 34 80 43 FOR ERECTION PLAN AND OTHER ERECTION AND FABRICATION SUBMITTAL




JULINA R. CORONA, P.E PROJECT MANAGER

	REINFO	RCING	SCHEDULE	
(QUANTITY	PER ON	E 42" DO	OUBLE CELL BO	X GIRDER)
REQ'D	MARK	SIZE	LENGTH	SHAPE
116	C409b	#4	4'-9"	
98	C711b	#4	7'-11''	C
36	C4806	#4	48'-6"	
116	D400b	* 5	4'-0"	J
98	D609	* 5	6'-9"	
80	D902b	*5	9'-2"	0
16	D1011b	*5	10' - 11''	
160	D1105b	* 5	11'-5''	
2	E309b	*6	3'-9''	
18	G4806	*8	48'-6"	

EST. WT. OF REINFORCING STEEL = 8.425 LB.

		WEIGHTS (O	NE GIRDER)	
NOMINAL	NOMINAL V	VEIGHT *	MAX LIFTING	WEIGHT **
GIRDER LENGTH (L)	WEI (WITH CURI	GHT B & WALK)		GHT B & WALK)
	LB.	TON	LB.	TON
49'	98,230	49.1	103,455	51.8

- * Computed weights using nominal dimensions. For planning purposes only. Fabricator to determine actual lifting weight. If scale weight not available, use maximum weights.
- ** Computed weights using maximum dimensions per allowable tolerances. Use for lifting weight if scale weight is not available.



BAR DESIGNATIONS CONSIST OF BAR SIZE & LENGTH FOLLOWED BY THE LETTER "b" IF BENT. BAR SIZES ARE REPRESENTED BY THE LETTERS A THROUGH L CORRESPONDING TO BAR SIZE *2 THROUGH *18. BAR LENGTHS ARE GIVEN IN FEET AND INCHES; THE LAST TWO DIGITS ARE INCHES.

	FINAL DESIGN (100%) CAMERA READY			All plans, drawings, specifi- cations, and or information furnished herewith shall remain the property of the Ventura County Transportation Commission and shall be held confidentials	DE
_	ADDED NOTE			for in agreements with the	AF
_	AUGU NOTE	BY SUB	APP.	Ventura Country Transportation Commission.	D

SIGNED BY K. THOMSEN	PROFESSION
AWN BY G. SMITH	C DAMMAD SA
ECKED BY H. YANG	SION C68399
PROVED BY M. SARWAR	EXP: 09-30-2
12-25-2023	PIE OF CALIFO






SESPE CREEK OVERFLOW BRIDGE REPAIR ON THE SANTA PAULA BRANCH LINE, FILLMORE, CA


GIRDER DETAILS NO. 2

CONTRACT NO. DRAWING NO. S-013 REVISION SHEET NO. 22 OF 30 SCALE AS SHOWN

REV. DATE

3/22/25





- HANDRAIL BASE PLATE (TYP.)


CONTRACT NO.


S-015

AS SHOWN

24 OF 30

REVISION SHEET NO.





	CEMENTATION
Description	Criteria
Weak	Crumbles or breaks with handling or little finger pressure.
Moderate	Crumbles or breaks with considerable finger pressure.
Strong	Will not crumble or break with finger pressure.

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	VENTURA	_	423.18	3	3
	Staphac ISTERED GEOTEC	M- O., HNICAL ENGINEER	3/24/25 PP DATE	OFESSIO, OPER N.	

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.


RAILPROS 250 COMMERCE STE 200 IRVINE, CALIFORNIA 92602


DIAZ YOURMAN & ASSOC. 1616 E 17TH STREET SANTA ANA, CALIFORNIA 92705


This LOTB sheet was prepared in accordance with the Caltrans Soil & Rock Logging, Classification, & Presentation Manual (2010).

BOREHOLE IDENTIFICATION				
Symbol	Hole Type	Description		
Size	A	Auger Boring (hollow or solid stem bucket)		
	R	Rotary drilled boring (conventional)		
Size	RW	Rotary drilled with self-casing wire-line		
	RC	Rotary core with continuously-sampled, self-casing wire-line		
	P	Rotary percussion boring (air)		
Size	R	Rotary drilled diamond core		
	HD	Hand driven (1-inch soil tube)		
N N N N N N N N N N N N N N N N N N N		Hand Auger		
		·		
0	D	Dynamic Cone Penetration Boring		
	CPT	Cone Penetration Test (ASTM D 5778)		
	0	Other (note on LOTB)		
		Note: Size in inches.		

CONSISTENCY OF COHESIVE SOILS				
Description	Shear Strength (tsf)	Pocket Penetrometer Measurement, PP, (tsf)	Torvane Measurement, TV, (tsf)	Vane Shear Measurement, VS, (tsf)
Very Soft	Less than 0.12	Less than 0.25	Less than 0.12	Less than 0.12
Soft	0.12 - 0.25	0.25 - 0.5	0.12 - 0.25	0.12 - 0.25
Medium Stiff	0.25 - 0.5	0.5 - 1	0.25 - 0.5	0.25 - 0.5
Stiff	0.5 - 1	1 - 2	0.5 - 1	0.5 - 1
Very Stiff	1 - 2	2 - 4	1 - 2	1 - 2
Hard	Greater than 2	Greater than 4	Greater than 2	Greater than 2







CONE PENETRATION TEST (CPT) BORING

FINAL DESIGN 100% CAMERA READY NOT FOR CONSTRUCTION

DESIGNED BY
A. SCHOLDER INFORMATION CONFIDENTIAL: All plans, drawings, specifications, and or information furnished herewith shall remain the property of the Southern California Regional Rail Authority and shall be held confidential; and shall or held confidential; and shall mot be used for any purpose not provided for in agreements with the Southern California Regional Rail Authority. A. SCHOLDER HECKED BY
T. REINERT PROVED BY C. DIAZ 12-28-2023

VENTURA COUNTY TRANSPORTATION COMMISSION

JULINA R. CORONA, P.E. PROJECT MANAGER

SESPE CREEK OVERFLOW BRIDGE REPAIR ON THE SANTA PAULA BRANCH LINE, FILLMORE, CA LOG OF TEST BORINGS

CONTRACT NO. DRAWING NO. GE-001 REVISION SHEET NO 27 OF 30 AS SHOWN

					ND NAME	
		Group Names		Graphic	c/Symbol	Group Names
	GW GP	Well-graded GRAVEL Well-graded GRAVEL with SAND Poorly-graded GRAVEL Poorly-graded GRAVEL with SAND			CL	Lean CLAY Lean CLAY with SAND Lean CLAY with GRAVEL SANDY lean CLAY SANDY lean CLAY GRAVELLY lean CLAY GRAVELLY lean CLAY
	GW-GM GW-GC	Well-graded GRAVEL with SILT Well-graded GRAVEL with SILT and SANI Well-graded GRAVEL with CLAY (or SILTY CLAY) Well-graded GRAVEL with CLAY and SAN (or SILTY CLAY and SAND)			CL-ML	SILTY CLAY SILTY CLAY with SAND SILTY CLAY with SAND SILTY CLAY with GRAVEL SANDY SILTY CLAY SANDY SILTY CLAY with GRAVEL GRAVELLY SILTY CLAY GRAVELLY SILTY CLAY
	GP-GM GP-GC	Poorly-graded GRAVEL with SILT Poorly-graded GRAVEL with SILT and SA Poorly-graded GRAVEL with CLAY (or SILTY CLAY)	ND		ML	SILT SILT with SAND SILT with GRAVEL SANDY SILT SANDY SILT with GRAVEL GRAVELLY SILT
	GM	Poorly-graded GRAVEL with CLAY and SAND (or SILTY CLAY and SAND) SILTY GRAVEL SILTY GRAVEL with SAND CLAYEY GRAVEL CLAYEY GRAVEL with SAND			OL	GRAVELLY SILT with SAND ORGANIC lean CLAY ORGANIC lean CLAY with SAND ORGANIC lean CLAY with GRAVEL SANDY ORGANIC lean CLAY SANDY ORGANIC lean CLAY SANDY ORGANIC lean CLAY with GRAVEL GRAVELLY ORGANIC lean CLAY GRAVELLY ORGANIC lean CLAY with SAND
	GC-GM SW	SILTY, CLAYEY GRAVEL SILTY, CLAYEY GRAVEL with SAND Well-graded SAND Well-graded SAND with GRAVEL			OL	ORGANIC SILT ORGANIC SILT with SAND ORGANIC SILT with GRAVEL SANDY ORGANIC SILT SANDY ORGANIC SILT with GRAVEL GRAVELLY ORGANIC SILT GRAVELLY ORGANIC SILT
	SP SW-SM	Poorly-graded SAND Poorly-graded SAND with GRAVEL Well-graded SAND with SILT Well-graded SAND with SILT and GRAVEL			СН	Fat CLAY Fat CLAY with SAND Fat CLAY with GRAVEL SANDY fat CLAY SANDY fat CLAY with GRAVEL GRAVELLY fat CLAY GRAVELLY fat CLAY GRAVELLY fat CLAY with SAND
	SW-SC SP-SM	Well-graded SAND with CLAY (or SILTY CLAY) Well-graded SAND with CLAY and GRAVEL (or SILTY CLAY and GRAVEL) Poorly-graded SAND with SILT Poorly-graded SAND with SILT and GRAVEL			МН	Elastic SILT Elastic SILT with SAND Elastic SILT with GRAVEL SANDY elastic SILT SANDY elastic SILT with GRAVEL GRAVELLY elastic SILT GRAVELLY elastic SILT with SAND
•	SP-SC	Poorly-graded SAND with CLAY (or SILTY CLAY) Poorly-graded SAND with CLAY and GRAVEL (or SILTY CLAY and GRAVEL) SILTY SAND			ОН	ORGANIC fat CLAY ORGANIC fat CLAY with SAND ORGANIC fat CLAY with GRAVEL SANDY ORGANIC fat CLAY SANDY ORGANIC fat CLAY GRAVELLY ORGANIC fat CLAY
	SC	SILTY SAND with GRAVEL CLAYEY SAND CLAYEY SAND with GRAVEL			ОН	GRAVELLY ORGANIC fat CLAY with SAND ORGANIC elastic SILT ORGANIC elastic SILT with SAND ORGANIC elastic SILT with GRAVEL SANDY ORGANIC elastic SILT SANDY ORGANIC elastic SILT with GRAVEL
77. 7 77. 7 11. 11. 11. 11. 11. 11. 11. 11. 11. 11.	SC-SM PT	SILTY, CLAYEY SAND SILTY, CLAYEY SAND with GRAVEL PEAT		J		GRAVELLY ORGANIC elastic SILT GRAVELLY ORGANIC elastic SILT with SAND ORGANIC SOIL ORGANIC SOIL with SAND
		COBBLES COBBLES and BOULDERS BOULDERS		ST ST 2 ST ST 2 ST ST 2 ST ST 2	OL/OH	ORGANIC SOIL with GRAVEL SANDY ORGANIC SOIL SANDY ORGANIC SOIL with GRAVEL GRAVELLY ORGANIC SOIL GRAVELLY ORGANIC SOIL with SAND
FINAL DESIGN 100% CAMERA READY NOT FOR CONSTRUCTION All plons, drowing and or furnished herewere the Southern Co. Regional Roil Australia and shall be held according to the control of the Southern Co. Regional Roil Australia and shall be held according to the Southern Co. Regional Roil Australia and shall be held according to the Communication of the Communicat			INFORMATION CONFIDEN All plans, drawings, sp. cations, and or inform furnished herewith sho remain the property o the Southern Colifornia Regional Rail Authority shall be held confiden and shall not be used any purpose not provi for in agreements with	ecifi- ation DRA I f the and tial; for	A. SCHOLD A. SCHOLD WN BY A. SCHOLD CKED BY T. REINER ROVED BY C. DIAZ	DER

FIELD AND LABORATORY **TESTING**

- Consolidation (ASTM D 2435)
- (CL) Collapse Potential (ASTM D 5333)
- Compaction Curve (CTM 216)
- Corrosivity Testing (CTM 643, CTM 422, CTM 417)
- Consolidated Undrained Triaxial (ASTM D 4767)
- (DS) Direct Shear (ASTM D 3080)
- (EI) Expansion Index (ASTM D 4829)
- Moisture Content (ASTM D 2216)
- Organic Content-% (ASTM D 2974)
- Permeability (CTM 220)
- Particle Size Analysis (ASTM D 422)
- Plasticity Index (AASHTO T 90) Liquid Limit (AASHTO T 89)
- (PL) Point Load Index (ASTM D 5731)
- Pressure Meter
- R-Value (CTM 301)
- Sand Equivalent (CTM 217)
- (SG) Specific Gravity (AASHTO T 100)
- (SL) Shrinkage Limit (ASTM D 427)
- (SW) Swell Potential (ASTM D 4546)
- Unconfined Compression-Soil (ASTM D 2166)
- Unconfined Compression-Rock (ASTM D 2938)
- Unconsolidated Undrained Triaxial (ASTM D 2850)
- (UW) Unit Weight (ASTM D 4767)

Dist	COUNTY	ROUTE	POST MILES TOTAL PROJECT	SHEET No.	TOTAL SHEETS
07	VENTURA	ı	423.18	3	3

No. 2992

Chataghan M. De 3/24/25
REGISTERED GEOTECHNICAL ENGINEER DATE /

PLANS APPROVAL DATE

THE STATE OF CALIFORNIA OR ITS OFFICERS OR AGENTS SHALL NOT BE RESPONSIBLE FOR THE ACCURACY OR COMPLETENESS OF SCANNED COPIES OF THIS PLAN SHEET.

RAILPROS 250 COMMERCE STE 200 IRVINE, CALIFORNIA 92602

DIAZ YOURMAN & ASSOC. 1616 E 17TH STREET SANTA ANA, CALIFORNIA 92705

This LOTB sheet was prepared in accordance with the Caltrans Soil & Rock Logging, Classification, & Presentation Manual (2010).

APPARENT DENSITY OF COHESIONLESS SOILS					
Description	SPT N ⁶⁰ (Blows / 12 in.)				
Very Loose	0 - 5				
Loose	5 - 10				
Medium Dense	10 - 30				
Dense	30 - 50				
Very Dense	Greater than 50				

<u> </u>			
MOISTURE			
Description	Criteria		
Dry	No discernable moisture		
Moist	Moisture present, but no free water		
Wet	Visible free water		

PERCENT OR PROPORTION OF SOILS				
Description	Criteria			
Trace	Particles are present but estimated to be less than 5%			
Few	5% - 10%			
Little	15% - 25%			
Some	30% - 45%			
Mostly	50% - 100%			

PARTICLE SIZE			
Des	scription	Size (in.)	
Boulder		Greater than 12	
Cobble		3 - 12	
Gravel	Coarse	3/4 - 3	
Gravei	Fine	1/5 - 3/4	
	Coarse	1/16 - 1/5	
Sand	Medium	1/64 - 1/16	
	Fine	1/300 - 1/64	
Silt and Clay		Less than 1/300	

VENTURA COUNTY TRANSPORTATION COMMISSION

> SUBMITTED: JULINA R. CORONA, P.E. PROJECT MANAGER

SESPE CREEK OVERFLOW BRIDGE REPAIR ON THE SANTA PAULA BRANCH LINE, FILLMORE, CA SOIL LEGEND 1 OF 2 - LOG OF TEST BORINGS

CONTRACT NO. DRAWING NO. GE-002 REVISION SHEET NO. 28 OF 30 AS SHOWN

FINAL DESIGN 100% CAMERA READY NOT FOR CONSTRUCTION

